

Scope of Work

Troup Co Jail Floor Covering Removal/Replacement

Description of Work and Supplies needed

LVT (Grey Mist)

Aladdin Commercial grey Mist Glue Down LVT approximately 15,331 SQFT + 10% wastes + 16,872 SQFT

Spread glue and install flooring

LVT Glue

Installation of 4" Rubber Base (Black)

JOHNSONITE 4" Rubber base 120 LINEAR FT

Commercial grade rubber flooring transition

Demo existing VCT

Demo Existing Carpet

Removal and haul away all debris

Notes:

ALL MAIN FURNITURE TO BE MOVED PRIOR TO START ANY PHASE READY FOR DEMO AND INSTALLATION.

Area	Sq. Ft.
Front Lobby Floors	2450
Admin Office Floors	9281
Tower Floors	3600
10%	1541
Total	16872